

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Schedule-B


NAME OF THE WORK: Filling of potholes in main and cross roads in Dasarahalli in ward no. 15
Dasarahalli sub division

Sl. No	Description of work	Unit	Qty	Rate to be Quoted	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	163.88	86.92	Rupees Eighty Six and Ninety Two Paise Only
2	KSRRB M400-17: Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam Specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per Specifications.MORTH Specification No. 406 with all leads and lifts etc., Complete as per the direction of Engineer-in-charge of the work (PWD SR 2016-17 Page No. 154/ Item No. 20.18/	Cum	95.69	1768.08	Rupees One Thousand Seven Hundred Sixty Eight and Eight Paise Only
3	Removal of all failed material, trimming of completed excavation to provide firm versal faces, cleaning of surface, painting of tack coat on the side and base of excavation as per clause 500.3, back filling the pot holes wiith hot bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications Filling opot holes and patch repairs with bituminous concrete, 40mm.(PWD SR 2016-17, P.No-257, I No-35.5)	Sqm	382.75	302.10	Rupees Three Hundred Two and Ten Paise Only


Signature of the Contractor


Executive Engineer,
Dasarahalli Division
BBMP

4	KSRRB M2100-10. Plain cement concrete M-10 with OPC cement at 220kg with crushed 40mm down size graded granite metal course aggregate @0.84 CUM and fine agreegate @ 0.6 CM in Foundation mechanically mixed placted in foundation and compacted by vibration including curing for 14 days complete as per specifications. MORTH Specification No. 2100. Page No. 218/ Item No. 27.18/ PWD SR 2016-17	Cum	49.05	5972.04	Rupees Five Thousand Nine Hundred Seventy Two and Four Paise Only
5	KSRRB M2200-5.9 Design Mix M20 with OPC cement @ 320kgs with 20mm & down size graded granite metal course agreegate @ 0.69 CM an Fine aggregated 0.46 cm with super plaster @ 3ltrs confirming to IS 9103-1999 Reaffirmed -2008 i.) Upto 5m height Page No. 223/ Item No. 28.7.9/ PWD SR 2016-17	Cum	49.05	6965.26	Rupees Six Thousand Nine Hundred Sixty Five and Twenty Six Paise Only
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 150 Item No. 17.1 PWD SR 2016-17	Cum	163.88	80.80	Rupees Eighty and Eighty Paise Only



Signature of the Contractor



Executive Engineer,
Dasarahalli Division
BBMP